



AECB
the sustainable building association

2010 Annual Conference
Celebrating 21 years of the AECB

**Something Old,
Something New**

1-2 October 2010 • WISE Building, CAT

Organised by:

AECB
the sustainable building association

In association with


**Passivhaus
Trust**
The UK Passive House Organisation

Designing & building a Passivhaus using standard UK building techniques



- The Clients



Longwood Low Energy House 1991



Why cavity wall?

Advantages

- Familiar method for UK builders
- West Yorkshire planning requirements
- Thermal mass – acts as a heat store
- Budget restraints

Disadvantages

- Harder to get air tightness detailing correct
- Harder to test as you are going along




Passivhaus standard

Air-tightness	0.6ach @ 50Pa	Comfort
Surface temp (windows)	>17degC	Comfort
Summer overheating	Max 10% >25degC	Comfort
Vent	~30m ³ /hr.person	Comfort
Heating	15kWh/m ² a	Energy
Primary Energy	120kWh/m ² a	Energy

PHPP software considers;

- U-values for all elements, windows, doors, walls, etc
- Thermal bridges
- Shading
- Window orientation
- Ventilation
- Climate
- Domestic hot water demand
- Solar domestic hot water
- Electricity
- Boilers

Preliminary Design 2007



Denby Dale Passivhaus 2009



Supported by:



Faculty of Arts & Society
School of the Built Environment

Key features

- Detached 3 bed dwelling with integral two storey sun space
- One of first certified Passivhaus buildings in the UK
- Expected to be the first Passivhaus built using traditional cavity wall construction
- £140K budget
- Build starting May 2009

Elevations


NOTES



ELEVATION TO ACCESS ROAD (south)
1:100 in A3/LA



ELEVATION TO BACK GARDEN (north)
1:100 in A3/LA



ELEVATION TO SIDE (west)
1:100 in A3/LA



ELEVATION TO SIDE (east)
1:100 in A3/LA

LO00

Public Planning Internal Consultation
Planning Number: 2016

Proposed detached dwelling
at the rear of 373 and 371 Wakefield Road
Derby Dale West Yorkshire


Client: Geoff and Kate Tunstall
373 & 371, Wakefield Road Derby, Dale West Yorkshire DE24 9DF

Derek O'Riordan Architects
29 Lincoln Road York YO1 1EF
Tel: 01904 788820 Fax: 01904 527 919
www.dora.co.uk

Design
Part 2/3


Completion of any further design work pending final Approvals and
planning consent to a variety of levels.

Floor plans



GROUND FLOOR PLAN

STAIRS: Main Staircase to be made of timber with timber treads. Dimensions to be taken on site - total height approximately 2750mm with 10 number stairs @ 170mm and gings @ 300mm with maximum angle of 35 degrees. Landing to have same going as width of stairs, ie 900mm between wall and balustrade/handrail. Minimum headroom to be 2.0m above platform, handrail to both sides of stairs to be 900mm above platform. Titrners: 3 x 60 x 100w. Guarding/balustrading to the stairs and landing to be plywood panels or plasterboard with skiv finish on 60 x70mm framing and hardwood handrails. Balustrade at top of stairs to be 900mm above the floor. Balustrade to the landing to be 1100mm above the floor. Opening between the balustrade and the handrail to be a maximum of 25 mm spacing.



FIRST FLOOR PLAN

PLUMBING INSTALLATION: Install sanitary fittings as decided on the plan. All sinks, showers, baths and basins to have re-sealing beds. Provide rodding eyes at all changes of direction. Wastes to basins to be 32mm upvc. All other wastes to be 32mm, to connect into existing underground drain. Provide access to base of soil stacks and connect branches with slow redus bends. UPVC soil vent pipes to have an automatic air admittance valve in accordance with manufacturers instructions or terminate 1.0m above the uppermost first floor windows. Rainwater down pipes and gutters to be zinc. Fit fire proof collars in pipes in floor.

HEATING INSTALLATION: Background/backup heating dhw to be provided by a Commissioning of Heating and HWG Installation, Inspection and Completion Certificates to be issued and be made available to the employer and the Building Control Authority.

NOTES

MECHANICAL VENTILATION: Mechanical Heat Recovery installation MVHR Thermo 200' manufactured by Paul and supplied/installed by the Green Store to provide full ventilation to all spaces and to exceed the minimum Approved Documents Requirements of Kitchen 60 litres/second, Utility 30 litres/second, Bath and ensuite 15 litres/second.

ELECTRICAL INSTALLATION: To conform to EE etc regulations. Install self contained - separate circuit - interlinked mains operated smoke detection and alarm to BS5839 PART 1 - L3 standard, located in all circulation areas within 1m of bedroom doors, 7m from habitable rooms. Agree positions on site with LA Building Inspector. One smoke detector per storey. Switches and sockets to be not less than 450mm and not more than 1200 above floor level. Install energy saving light sockets at a ratio of 1 each in 3.

LOG

Date of Planning Approval: 20/06/2019
Planning Approval: 0260

Proposed detached dwelling
at the rear of 373 and 371 Wakefield Road
Denby Dale West Yorkshire

Client: Geoff and Kate Turrell
373 & 371 Wakefield Road Denby Dale West Yorkshire HD9 2PP

Design Certificate

12 House Road Wakefield WF1 3JF
Tel: 01924 244222 Fax: 01924 227 418
www.gbs.co.uk

Design Certificate

Completion of building design services including final inspection and approval subject to a copy of title.

Key features of Passivhaus

- Super insulation
- Minimising thermal bridging
- Stringent airtightness measures
- Minimising thermal bypass

- Mechanical ventilation heat recovery (MVHR)

Super insulation

**Target: U-value of less than 0.15
W/m²K for external envelope.**

- Cavity (300mm) fibreglass batts
- Roof void (500mm) fibreglass quilt
- Under groundfloor (225mm) polyfoam insulation.

**Target: combined U-value of 0.8
W/m²K for windows**



Minimising thermal bridging

Measures taken to minimise thermal bridging at junctions (eg between the ground floor and walls and at window and door openings).



Stringent airtightness measures

Leakage target: less than 1m³/h/m².


Measures include:

- Wet plaster coating to interior walls
- Floor slab carried across the top of the blockwork of the inner leaf of the wall
- Attention to airtightness detail around window and door openings and junctions between floors, walls and roofs.




Minimising thermal bypass


Minimisation of air movement around insulation in cavity wall and roof void through windtightness detailing



Infiltration of external air by natural or forced (wind) convection




Ventilation or venting



Air rotation by natural convection around insulation


Mechanical ventilation with heat recovery (MVHR)

The PAUL Comfort Ventilation system used can transfer up to 90% of the heat from the outgoing air to the incoming air.



The effect of window position and insulation wrapping


$$U_w \text{ inst.}^* = 1.84 \text{ W/m}^2\text{K}$$



Schematic drawing based on an example from proceedings of the Passive House Conference 2006 for renovation of typical German construction using PH standard window. Freundorfer, Kaufmann and Krause


*1m x 1m window

The effect of window position and insulation wrapping




Schematic drawing based on an example from proceedings of the Passive House Conference 2006 for renovation of typical German construction using PH standard window. Freundorfer, Kaufmann and Krause

Conventional detail



Denby Dale detail



Conventional detail

Data column	Row	Name	Ufactor name	Length mm	U factor	L2D W/Km
S	17	L2D Uf	External	318.56	0.7921	0.2523
T	16	L2D inc glass	External	322.55	0.8090	0.2609
U	17	L2D inc Wall	Internal	1299.24	0.3130	0.4067
V	17	wall	internal	1000.00	0.1014	0.1014
W	17					
X	17					

Uframe for EN 10077-2 Window Calc.		dimension mm	U-value W/m2K	heat flow W/mK
L2D with insulation replacing glazing				0.2523
Glass	from model	thickness 44	0.701	
		width 190		0.1331
Frame	from model	127	U Frame 0.939	

Psi Spacer for EN 10077-2 Window Calc		dimension mm	U-value W/m2K	heat flow W/mK
L2D with glazing				0.2609
Glass	from model	width 190	0.620	0.1178
Frame		width 127	0.939	0.1192
			Psi Spacer 0.024	

Psi Window Installation according to Pa:		dimension mm	U-value W/m2K	heat flow W/mK
L2D with wall				0.4067
L2D without wall				0.2609
Wall	from model	1020	0.101	0.1034
			Psi Installation 0.042	

$\Psi_{inst} 0.042 \text{ W/m}^2\text{K}$

Denby Dale detail

Data column	Row	Name	Ufactor name	Length mm	U factor	L2D W/Km
S	16	L2D Uf	External	317.00	0.7933	0.2515
T	16	L2D inc glass	External	322.55	0.8100	0.2613
U	17	L2D inc Wall	Internal	1342.55	0.2690	0.3611
V	17	wall	Internal	1000.00	0.1014	0.1014
W	17					
X	17					

Uframe for EN 10077-2 Window Calc.		dimension mm	U-value W/m2K	heat flow W/mK
L2D with insulation replacing glazing				0.2515
Glass	from model	thickness 44	0.701	
		width 190		0.1331
Frame	from model	127	U Frame 0.932	

Psi Spacer for EN 10077-2 Window Calc		dimension mm	U-value W/m2K	heat flow W/mK
L2D with glazing				0.2613
Glass	from model	width 190	0.620	0.1178
Frame		width 127	0.932	0.1183
			Psi Spacer 0.025	

Psi Window Installation according to Pa:		dimension mm	U-value W/m2K	heat flow W/mK
L2D with wall				0.3611
L2D without wall				0.2613
Wall	from model	1020	0.1014	0.1034
			Psi Installation -0.004	

$\Psi_{inst} -0.004 \text{ W/m}^2\text{K}$


Conventional detail

Treated Floor Area:		104.4 m ²					
	Applied:	Monthly Method	PH Certificate:			Fulfilled?	
Specific Space Heat Demand:	16	kWh/(m ² a)	15 kWh/(m ² a)			No	
Pressurization Test Result:	0.3	h ⁻¹	0.6 h ⁻¹			Yes	
Specific Primary Energy Demand (DHW, Heating, Cooling, Auxiliary and Household Electricity):	82	kWh/(m ² a)	120 kWh/(m ² a)			Yes	
Specific Primary Energy Demand (DHW, Heating and Auxiliary Electricity):	42	kWh/(m ² a)					
Specific Primary Energy Demand Energy Conservation by Solar Electricity:		kWh/(m ² a)					
Heating Load:	11	W/m ²					
Frequency of Overheating:	2	%	over 25 °C				
Specific Useful Cooling Energy Demand:		kWh/(m ² a)	15 kWh/(m ² a)				
Cooling Load:	11	W/m ²					

Denby Dale detail

Treated Floor Area:		104.4 m ²					
	Applied:	Monthly Method	PH Certificate:			Fulfilled?	
Specific Space Heat Demand:	14	kWh/(m ² a)	15 kWh/(m ² a)			Yes	
Pressurization Test Result:	0.3	h ⁻¹	0.6 h ⁻¹			Yes	
Specific Primary Energy Demand (DHW, Heating, Cooling, Auxiliary and Household Electricity):	80	kWh/(m ² a)	120 kWh/(m ² a)			Yes	
Specific Primary Energy Demand (DHW, Heating and Auxiliary Electricity):	40	kWh/(m ² a)					
Specific Primary Energy Demand Energy Conservation by Solar Electricity:		kWh/(m ² a)					
Heating Load:	11	W/m ²					
Frequency of Overheating:	2	%	over 25 °C				
Specific Useful Cooling Energy Demand:		kWh/(m ² a)	15 kWh/(m ² a)				
Cooling Load:	11	W/m ²					


Strip Foundation and Ground Floor Slab to External Wall Junction









Intermediate Floor to External Wall Junction







Window External Wall Junction and Optimising Performance



Installed U Value **0.75 W/m²K**













External Door Threshold Detail





Roof External Wall Junction















Performance Results

- $0.31 \text{ m}^3/(\text{hm}^2) @ 50\text{Pa}$
- Part L requires $10 \text{ m}^3/(\text{hm}^2) @ 50\text{Pa}$

- $0.33 \text{ ac}/\text{m}^2/\text{hr}$
- Passivhaus requires $0.6 \text{ ac}/\text{m}^2/\text{hr}$

- Space heating need $13 \text{ kWh}/\text{m}^2/\text{annum}?$
- Passivhaus requires $15 \text{ kWh}/\text{m}^2/\text{annum}$









Documentary Evidence

- Full set of drawings including shading, construction detailing, M&E layouts, etc
- Technical Specification particularly U values for all relevant components and materials
- Technical Specification for ventilation and heating including commissioning data
- Air Tightness certification
- Declaration from Construction Supervisor
- Full photographic evidence

On site lessons

- The necessity for clear well thought through and consistent detailing
- The need for open communication channels between the design and construction sides of the 'team'
- Imperative to share all knowledge of 'why and how' between all involved, from designers to site operatives
- There is no substitution for care with pride

High quality construction?

- Traditional building process

Partner-activity	Fases						
	order	sketch-design	pre-design	Final design	Execution	Lead	After sale services
Builder							
Architect							
Engineering							
Constructor							

High quality construction?

- Improved building process

Partner-activity	Fases						
	order	sketch-design	pre-design	Final design	Execution	Lead	After sale services
Builder	DESIGNTEAM						
Architect							
Engineering							
Constructor							

High quality construction?

- Passive House building process

Partner-activity	Fases						
	order	sketch-design	pre-design	Final design	Execution	Lead	After sale services
Builder	<h1>Buildingteam</h1>						
Architect							
Engineering							
Constructor							

- The Clients



- The Builders



- The Heating Engineers



- The Architect



Passivhaus diaries, part 21: Certification! | Online News | Building - Mozilla Firefox


File Edit View History Bookmarks Tools Help

http://www.building.co.uk/comment/passivhaus-diaries-part-21-certification/3162968.article

Passivhaus diaries, part 21: Certifica...

Welcome Chayley Cole Sign Out My Account Latest Issue Subscribe to Building Advertise

RECRUITING FOR 'HEAD OF SUSTAINABLE REFURBISHMENT'



Send us Feedback
Tell us your thoughts on our new website's design and features...


Building.co.uk | Tuesday, 20 September 2010

Search Building

HOME NEWS COMMENT **SECTORS** BUILDINGS TECHNICAL DATA Q&A LEGAL CAREERS NETWORK TV Jobs Events

BLOGS OPEN MID COLUMNS BUY & PRINT HANDBOOK WINNERS & BLUNDERS WHAT YOU THINK LEADER





HOME | COMMENT



Bill Butcher
The Denby Dale home project draws to an end


Passivhaus diaries, part 21: Certification!


30 April 2010 | By Bill Butcher

PRINT EMAIL SHARE    COMMENTS (7) 

Today the Denby Dale Passivhaus gets its official certification - one of the first three projects to be certified today by Pete Warm of WARM Low Energy Building Practice (and verified by the Passivhaus Institut in Germany). We had a party at the house on Monday in anticipation of this, attended by all the team (architect, clients, builders) as well as supportive local councillors and officials from our progressive council, Kirklees, presided over by the mayor of Kirklees herself. Much cake was consumed and tea drunk and it was great to be able to see the house looking lovely and fresh and bright, without scaffolding and building site mess. There will be an official Passivhaus plaque and certificate coming our way soon and it will be very nice for me to wave a copy of it at the Passivhaus conference in Dresden when I go there in May.

Certification process Passivhaus is a clearly defined standard for low energy building developed by the Passivhaus Institut in Germany. There is now a handful of Passivhaus certifying bodies in the UK - BRE, Inbuilt, Scottish Passive House Centre and WARM. To become a member, contact www.passivhaus.org.uk






This is worth talking about

thisisconcrete.co.uk

twitter.com/thisisconcrete

Supported by  **mpa**
The Concrete Centre

Most popular Most commented Most emailed

- 1 WYG completes restructure after £22m loss
- 2 Davis Langdon aims to become 'the next McKinsey'
- 3 Morgan Sindall scoops £17m university job
- 4 Peter Murray recovering after cycling accident
- 5 Abramovich building secret £20m nightclub

http://www.building.co.uk/comment/passivhaus-diaries-part-21-certification/3162968.article#comments

start Windows Explorer Microsoft Office Sustainability Awareness YouTube - Forward... Passivhaus Diaries... Downloads 14:23